

PRECAST CONCRETE SWIMMING POOL

GENERAL NOTES

- THE POOL INSTALLER SHALL BE RESPONSIBLE FOR MAINTAINING STABILITY OF THE STRUCTURE UNTIL COMPLETION OF CONSTRUCTION AND SHALL ENSURE THAT NO PART OF THE STRUCTURE IS OVER STRESSED BY EXCESSIVE CONSTRUCTION LOADING.
- TEMPORARY WORKS ARE THE RESPONSIBILITY OF THE POOL INSTALLER, THESE INCLUDE SUCH ITEMS AS TEMPORARY SHORING & RETENTION, MAINTAINING TEMPORARY STABILITY OF THE STRUCTURE, FORMWORK, CRANE BASE, TEMPORARY WORKING PLATFORMS AND GROUND IMPROVEMENT TO SUPPORT CONSTRUCTION PLANT.
- STRUCTURAL DRAWINGS TO BE READ IN CONJUNCTION WITH ALL POOL INSTALLER AND OTHER CONSULTANTS DRAWINGS AND SPECIFICATION.
- ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE FOLLOWING CODES EXCEPT WHERE VARIED BY THE DRAWINGS:
 - AS1170.0-2002 STRUCTURAL DESIGN ACTIONS – PART 0: GENERAL PRINCIPLES
 - AS1170.1-2002 STRUCTURAL DESIGN ACTIONS – PART 1: PERMANENT, IMPOSED AND OTHER ACTIONS
 - AS2783-1992 USE OF REINFORCED CONCRETE FOR SMALL SWIMMING POOLS
 - AS2870-2011 RESIDENTIAL SLABS AND FOOTINGS
 - AS3600-2018 CONCRETE STRUCTURES
 - AS4678-2002 EARTH-RETAINING STRUCTURES
- THE CODES, NOTES AND PROCEDURES REFERRED TO AND SHOWN ON THESE DRAWINGS APPLY AT THE TIME OF THE DRAWING ISSUE AND FOR A PERIOD OF 5 YEARS MAXIMUM THEREAFTER. WITH CONTINUED USE OVER A LONG PERIOD, THE CODES, NOTES AND PROCEDURES MAY BE SUBJECT TO ALTERATIONS AND MODIFICATIONS TO THIS DRAWING MAY BE REQUIRED. THE DETAILS ON THESE DRAWINGS ARE PROVIDED ON GOOD FAITH THAT GEOTECHNICAL INVESTIGATION IS CARRIED OUT PRIOR TO INSTALLATION OF THE POOL AND THE GEOTECHNICAL RECOMMENDATIONS AND REPORT ARE PROVIDED BY THE CUSTOMER TO AN INDEPENDENT CERTIFIED STRUCTURAL ENGINEER FOR VERIFICATION. BLIGH TANNER CARRIES NO RESPONSIBILITY FOR THE POOL SHELL IF NOT INSTALLED IN ACCORDANCE WITH GEOTECHNICAL RECOMMENDATIONS AND DESIGN ASSUMPTIONS OUTLINED IN THESE DRAWINGS.
- THE DETAILS ON THESE DRAWING APPLY ONLY FOR THE STANDARD POOL SHELL SIZE NOTED ON THE DRAWINGS.
- THESE DRAWINGS DETAIL THE STRUCTURAL DESIGN OF THE POOL SHELL ONLY. ALL OTHER CERTIFICATION AND BUILDING REGULATION REQUIREMENTS INCLUDING SKIMMER BOX INSTALLATION, POOL WATER TREATMENT, DRAINAGE REQUIREMENTS, POOL FENCING, ELECTRICAL AND EARTHING REQUIREMENTS, COUNCIL SUBMISSIONS AND APPROVALS, ETC ARE THE RESPONSIBILITY OF THE CUSTOMER.
- POOL INSTALLER TO ENSURE ANY FOOTING OR ADJOINING STRUCTURES ARE NOT UNDERMINED BY POOL EXCAVATION. ANY UNDERPINNING WORKS REQUIRED SHALL BE SUBJECT TO DESIGN AND CERTIFICATION BY AN INDEPENDENT CERTIFIED STRUCTURAL ENGINEER. UNDERPINNING WORKS TO BE DONE BEFORE EXCAVATION.
- CUSTOMER AND POOL INSTALLER TO MAKE THEMSELVES AWARE OF ANY IN-GROUND SERVICES AND AVOID ANY CLASHES WITH POOL EXCAVATION ZONE PRIOR TO EXCAVATION.

SALT WATER POOL

- IF SALT CHLORINATOR USED, CONCENTRATION TO BE KEPT BELOW 8,000 P.P.M

DESIGN CRITERIA

- ALL LOADINGS HAVE BEEN ASSESSED IN ACCORDANCE WITH AS1170 AND AS2783.
- THE STRUCTURAL COMPONENTS ON THESE DRAWINGS HAVE BEEN DESIGNED FOR THE FOLLOWING LOADINGS:
 - a. WATER PRESSURE – POOL WATER AT LEVEL SHOWN ON DRAWINGS.
 - b. GROUNDWATER PRESSURE – GROUNDWATER LEVEL TAKEN AT TOP OF POOL WALLS.
 - c. LATERAL EARTH PRESSURES –REFER FOUNDATIONS' NOTES.
 - d. LIVE LOADING = 0.8kN
 - e. SURCHARGE LOADING = 5kPa
 - f. INSTALLATION LOADS – AS SHOWN ON DRAWINGS.
- THE GEOTECHNICAL SITE CONDITIONS ARE A CRUCIAL COMPONENT IN THE DESIGN AND INSTALLATION OF THE POOL SHELL. IT IS THE RESPONSIBILITY OF THE CUSTOMER IS TO CONFIRM THE GEOTECHNICAL PARAMETERS FOR EACH SITE. REFER TO 'FOUNDATIONS' NOTES FOR MORE INFORMATION.
- THE DESIGN THE DESIGN REQUIRES THAT GROUND WATER PRESSURE TO THE POOL WALLS AND FLOOR SLAB BE RELIEVED BY INSTALLATION OF HYDROSTATIC VALVE WITH MAIN DRAIN DETAIL.
- THE POOL SHALL ONLY BE EMPTIED IN AN APPROVED MANNER UNDER PROPERLY CONTROLLED CONDITIONS. OWNER TO CONDUCT REGULAR (YEARLY) MAINTENANCE CHECKS OF THE DRAIN VALVE TO ENSURE THAT MAIN DRAIN VALVE DOES NOT BECOME BLOCKED. IT IS CRUCIAL THAT THE OWNER CHECKS THAT THE DRAIN VALVE IS NOT BLOCKED AND IS FULLY FUNCTIONING PRIOR TO EMPTYING POOL.
- OWNER TO ENSURE POOL REMAINS FULL IN THE EVENT OF FLOODING OR GENERAL RISE IN WATER TABLE LEVEL.
- THE DESIGN ASSUMES THAT THE SITE IS RELATIVELY FLAT WITH GROUND SLOPING AWAY FROM POOL.
- IT IS IMPORTANT THAT THE SITE BE WELL DRAINED. THE GROUND AROUND THE STRUCTURES SHOULD SLOPE AWAY AT 1 IN 50 AND THEN FALL TO THE STORMWATER SYSTEM TO PREVENT PONDING OF WATER AGAINST OR NEAR THE SURFACE OF THE POOL.

FOUNDATIONS

- THE CUSTOMER SHALL ENGAGE A CERTIFIED GEOTECHNICAL ENGINEER TO CARRY OUT SOIL TESTING AND PROVIDE ADVICE PRIOR TO COMMENCING WORKS ON SITE. THE AIM OF THE GEOTECHNICAL INVESTIGATION IS TO PROVIDE ADVICE ON THE FOLLOWING ASPECTS OF THE SITE:
 - a. GENERAL SITE CONDITIONS, INCLUDING PHOTOS;
 - b. SUBSURFACE CONDITIONS INCLUDING GROUNDWATER PRESENCE (AS LOCATED);
 - c. RECOMMENDATIONS OF DEWATERING RECOMMENDATIONS DURING EXCAVATION;
 - d. DEPTH TO SUITABLE BEARING STRATA;
 - e. EARTHWORKS CONSTRUCTION RECOMMENDATIONS INCLUDING SITE EXCAVABILITY, FILL PLACEMENT SPECIFICATION, SUBGRADE PREPARATION RECOMMENDATIONS AND COMPACTION PROCEDURES AND SPECIFICATION;
 - f. PREDICTED CHARACTERISTIC SURFACE MOVEMENT, SOIL SUCTION ZONE AND SITE CLASSIFICATIONS BASED ON SITE REACTIVITY IN ACCORDANCE WITH AS2870, INCLUDING THE EFFECT OF TREES PRESENCE NEAR THE PROPOSED POOL LOCATION;
 - g. SITE CONSTRAINTS AND CONSTRUCTION CONSIDERATIONS THAT MAY IMPACT SETOUT OF PROPOSED POOL LAYOUT, INCLUDING SLOPING SITES, EXISTING BUILDING FOUNDATIONS AND EXISTING TREES;
 - h. RECOMMENDATIONS ON WHETHER THE EXCAVATED SOILS CAN BE USED AS STRUCTURAL FILL;
 - i. MAINTENANCE PROGRAMMES FOR TREES, DRAINAGE, ETC
 - j. MAXIMUM TEMPORARY AND PERMANENT BATTER SLOPES FOR BOTH FILL PLATFORMS AND CUTTINGS;
 - k. LATERAL EARTH PRESSURES AGAINST THE WALLS;
 - l. RECOMMENDATIONS ON FOOTING TYPES AND DESIGN PARAMETERS FOR HIGH LEVEL OR DEEP FOOTINGS;
 - m. FIELDWORK COMPRISING OF MINIMUM 2 BOREHOLES (MINIMUM 6M DEPTH) TO BE UNDERTAKEN AT THE LOCATION OF WHERE THE POOL IS TO BE CONSTRUCTED;
 - n. LABORATORY TESTING OF SOIL, GROUNDWATER AND ROCK TO PROVIDE DATA FOR GEOTECHNICAL PARAMETERS ASSESSMENT AS REQUIRED INCLUDING:
 - i. MOISTURE CONTENT (MC);
 - ii. ATTERBERG LIMITS; AND
 - iii. PARTICLE SIZE DISTRIBUTION.
 - o. POTENTIAL PRESENCE OF ACID SULPHATE SOILS; AND
 - p. CONFIRM ALL GEOTECHNICAL ASSUMPTIONS USED IN DESIGN OF POOL SHELL:
 - i. MAXIMUM UNIT WEIGHT OF SOIL = 19kN/m³
 - ii. LONG TERM DRAINED $f = 28^{\circ}$ (AT REST' EARTH PRESSURE COEFFICIENT, $K_0 = 0.55$)
 - iii. MINIMUM ALLOWABLE BEARING PRESSURE = 100kPa.
- THE SCOPE OF THE GEOTECHNICAL INVESTIGATION SHOULD ALSO NOTE THE FOLLOWING GENERAL REQUIREMENTS:
 - a. THE FIELD WORK AND TESTING SHOULD BE CARRIED OUT UNDER THE SUPERVISION OF A QUALIFIED (RPEQ) GEOTECHNICAL ENGINEER, AND ONCE SAMPLES ARE RETURNED TO THE LABORATORY, THE LOGS PREPARED BY THE DRILLERS OPERATING THE DRILLING RIG ARE TO BE CHECKED AND VERIFIED.
 - b. TESTING OF SAMPLES IS TO BE UNDERTAKEN IN AN NATA ACCREDITED LABORATORY. THE SCOPE OF THE SOIL INVESTIGATION SHOULD BE UNDERTAKEN WITH REFERENCE TO APPROPRIATE SAMPLING GUIDELINES AND AS1726.
- THE GEOTECHNICAL CONSULTANT IS TO MAKE THEMSELVES AWARE OF ALL SERVICES AND EXISTING CONDITIONS IN THE AREA OF INVESTIGATION AND IS RESPONSIBLE FOR SAFETY OF PERSONNEL AND OTHERS ON SITE DURING SITE INVESTIGATION ACTIVITIES (I.E DIAL BEFORE YOU DIG, ETC).
- THE STANDARD POOL SHELL DESIGN IS SUITABLE FOR CONSTRUCTION IN SITES OF CLASSIFICATION A, S AND M IN ACCORDANCE WITH AS2870. THIS STANDARD POOL SHELL DESIGN IS NOT SUITABLE FOR CONSTRUCTION IN SITES OF CLASSIFICATION E, H1, H2 OR P. WITHOUT REINFORCED BASE SLAB, GROUND IMPROVEMENT WORKS OR ADDITIONAL DEEP FOUNDATIONS.
- FOUNDATIONS EXCAVATIONS TO BE MAINTAINED IN A FIRM DRY CONDITION. ALL UNCONTROLLED FILL, TOPSOIL AND ORGANIC MATTER UNDER POOL IS TO BE REMOVED.
- EXCAVATION SHALL NOT BE PERFORMED BELOW THE LINE OF INFLUENCE EXTENDING FROM THE EXISTING FOOTINGS AS PROVIDED BY THE GEOTECHNICAL ENGINEER.
- ALL FOUNDATIONS SHALL BE COMPACTED IN ACCORDANCE WITH GEOTECHNICAL REPORT RECOMMENDATIONS AND FOUNDED ON UNDISTURBED SOUND NATURAL GROUND CAPABLE OF WITHSTANDING A MINIMUM ALLOWABLE BEARING PRESSURE OF NOT LESS THAN 100kPa.
- UNLESS OTHERWISE SPECIFIED BY THE GEOTECHNICAL ENGINEER, STRUCTURAL FILL TO BE NONREACTIVE CBR15 PLACED IN 200 THICK LOOSE LAYERS AND COMPACTED TO 98% M.D.D.
- WHERE THERE ARE ANY VARYING FOUNDATIONS OVER POOL AREA OR WHERE UNDISTURBED SOUND NATURAL GROUND IS NOT ENCOUNTERED, GEOTECHNICAL ENGINEER TO PROVIDE RECOMMENDATIONS ON GROUND IMPROVEMENT WORKS OR PROVIDE SUITABLE RELOCATION OF PROPOSED POOL AREA TO ACHIEVE COMPLIANCE WITH STRUCTURAL AND GEOTECHNICAL DESIGN CRITERIA.

CONCRETE


- C1 CONCRETE SPECIFICATION
- SLUMP FLOW 650 +/- 40mm
 MAXIMUM AGGREGATE 10 mm
 CEMENT GP
- PROJECT CONTROL TESTING SHALL BE CARRIED OUT IN ACCORDANCE WITH AS.3600 AND THE SPECIFICATION TEST REPORTS TO BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR APPROVAL.
- C2 CONCRETE STRENGTH & CLEAR COVER TO BE AS FOLLOWS

ELEMENT	CONCRETE GRADE	COVER		
		BOTTOM	TOP	SIDES
PRECAST SHELL	S50	30	30	30
BASE SLAB	N32	50	50	50

- C3 CURE ALL CONCRETE SURFACES IN ACCORDANCE WITH AS.3600. CURING OF ALL CONCRETE IS TO BE ACHIEVED BY KEEPING SURFACES CONTINUOUSLY WET FOR A PERIOD OF 3 DAYS AND PREVENTION OF LOSS OF MOISTURE FOR A TOTAL OF 7 DAYS FOLLOWED BY A GRADUAL DRYING OUT. CURING COMPOUNDS NOT TO BE USED AS THEY MAY INHIBIT THE BOND OF SUBSEQUENT COATINGS.
- C4 ALL RE-ENTRANT CORNERS AND PENETRATIONS LARGER THAN 200 DIAMETER ARE TO HAVE TRIMMER BARS PLACED AT CORNERS. TRIMMER BARS SHALL BE 1 N10 x 500 LONG UNO.
- C5 ALL HOOKS AND BENDS TO BE IN ACCORDANCE WITH AS.3600. UNLESS NOTED OTHERWISE ALL LAPS TO BE :

BAR SIZE	LAP (mm)
N10	250

- C6 BASIC DRYING SHRINKAGE STRAIN MEASURED IN ACCORDANCE WITH AS.1012- PART 13 SHALL NOT EXCEED 800 µm.
- C7 CONDUITS, PIPES, ETC SHALL ONLY BE LOCATED IN THE MIDDLE ONE THIRD OF SLAB DEPTH AND SPACED AT NOT LESS THAN 3 DIAMETERS.
- C8 REINFORCEMENT SYMBOLS
 'N' - DENOTES GRADE 500 BARS TO AS.4671.
 'R' - DENOTES GRADE 250 HOT ROLLED PLAIN BARS TO AS.4671.



- C9 ALL CONCRETE TO BE VIBRATED DURING PLACEMENT.
- C10 IT IS CRITICAL TO CONSTRUCT SLAB AND WALLS WITH CORRECT COVER TO REINFORCEMENT. REINFORCEMENT HAVE MINIMAL TOLERANCE AND ACCURATE SETOUT IS TO BE CONFIRMED BY SURVEY PRIOR TO CASTING.
- C11 REINFORCEMENT SHALL BE ACCURATELY BENT AROUND CURVATURES IN THE POOL PROFILE SHOWN ON THE DRAWINGS.
- C12 THE REINFORCEMENT STEEL SUPPLIER MUST BE CERTIFIED BY ARCS (AUSTRALIAN STANDARDS CERTIFICATION & VERIFICATION OF REINFORCING, PRESTRESSING AND STRUCTURAL STEELS) FOR THE SUPPLY OF REINFORCEMENT STEEL. REFER www.steelcertification.com FOR CURRENT CERTIFICATE HOLDERS.
- C13 CONCRETE FINISH, TOLERANCES AND TONAL RANGE TO BE IN ACCORDANCE WITH CLASS 2 FINISH AS PER AS3610. ADDITIONAL FINISH REQUIREMENTS:
 - NO CHIPS OVER 25mm DIAMETER
 - NO AIR BUBBLES OVER 10mm DIAMETER
 - NO HAIRLINE CRACKS OVER 100mm LONG

ABBREVIATIONS


ABBREVIATION	DESCRIPTION	ABBREVIATION	DESCRIPTION
HORIZ	HORIZONTAL	(o)	OVER
VERT	VERTICAL	(u)	UNDER
CENT	CENTRALLY PLACED	LG	LENGTH/LONG
CRS	CENTRES	w	WIDTH/WIDE
C/W	COMES WITH	h	HEIGHT/HIGH
B or BTM	BOTTOM FACE	d	DEPTH/DEEP
T	TOP FACE	NOM	NOMINAL
T&B	TOP & BOTTOM	REQ'D	REQUIRED
NF	NEAR FACE	REINF	REINFORCEMENT
FF	FAR FACE	OPP	OPPOSITE
EF	EACH FACE	SIM	SIMILAR
EW	EACH WAY	GA	GENERAL ARRANGEMENT
EQ	EQUAL	PT	POST TENSION
NSOP	NOT SHOWN ON PLAN	DRG	DRAWING
NSOE	NOT SHOWN ON ELEVATION	NTS	NOT TO SCALE
UNO	UNLESS NOTED OTHERWISE	LL	LIVE LOAD
TYP	TYPICAL	FL	FLOOR LOAD
CL	CENTRE LINE	SDL	SUPERIMPOSED DEAD LOAD
PL	PLATE	THRU	THROUGH
CFW	CONTINUOUS FILLET WELD	NLB	NON LOAD BEARING
CPBW	COMPLETE PENETRATION BUTT WELD	MAX	MAXIMUM
		MIN	MINIMUM

PRECAST LIFTING AND INSTALLATION

- PRECAST SHELL TO BE CAST WITH MINIMUM S50 CONCRETE. REFER CONCRETE NOTES.
- REFER STRUCTURAL DRAWINGS FOR MINIMUM IN-SERVICE LOAD REINFORCEMENT. ALL DETAILS SHOWN ARE FOR WHEN PRECAST SHELL IS IN PLACE.
- LIFTING INSERTS HAVE BEEN DESIGNED TO THE LOADS AS SHOWN ON THE DRAWINGS. ANY ADDITIONAL LIFTING STRESSES MUST BE CHECKED BY THE LIFTING CONTRACTOR PRIOR TO LIFTING.
- LIFT PRECAST SHELL WITH SPREADER BAR AND PULLEYS AND LIFTING ROPES TO ENSURE EVEN LIFT & LOADING TO FERRULES. THE LIFTING CONTRACTOR MUST CHECK THE CAPACITY OF THE CAST IN FERRULES AGAINST THEIR TYPE OF LIFTING EQUIPMENT AND THE STRENGTH OF THE CONCRETE AT THE TIME OF LIFTING.
- LIFTING LOADS ON PRECAST SHELL MUST ADHERE TO THE FOLLOWING:
 - a. REMOVAL OF FORM AND LIFTING/ROTATING – FERRULES TO TAKE SHEAR LOADS ONLY. ROTATING OF PRECAST SHELL TO BE CARRIED OUT IN A SAFE AND CONTROLLED MANNER TO LIMIT WORKING SHEAR LOADS ON FERRULES AS SHOWN ON DRAWINGS.
 - b. DURING INSTALLATION – FERRULES TO TAKE WORKING LOADS AS SHOWN ON DRAWINGS.
- LIFTING CONTRACTOR TO ALLOW CONTROL TESTING OF CONCRETE SAMPLES TO CONFIRM MINIMUM CONCRETE STRENGTH AT TIME OF REMOVAL OF FORMS, LIFTING AND ROTATING AND INSTALLATION. MINIMUM CONCRETE STRENGTH FOR LIFTING TIMES ARE TO BE:
 - a. REMOVAL OF FORMS AND LIFTING/ROTATING OF PRECAST SHELL: 25MPa
 - b. DURING INSTALLATION: 50MPa
- LIFTING CONTRACTOR TO ENSURE PRECAST SHELL IS STABLE AND SECURED PRIOR TO INSTALLATION.
- CUSTOMER IS RESPONSIBLE FOR PROVIDING THE REQUIRED COUNCIL APPROVALS AND FORM 17 FINAL INSPECTION CERTIFICATE FOR THE PRECAST SHELL AND ENSURING THAT INSTALLATION COMPLIES WITH THE REQUIREMENTS SHOWN ON THE STRUCTURAL DRAWINGS.


REV	DATE	DESCRIPTION	DESIGN	DRAWN	CHECKED	APPROVED	RPEQ No.	PROJECT	DRAWING TITLE	SCALES	JOB NO	DRAWING NUMBER	REVISION
P1	17.07.2019	PRELIMINARY ISSUE	MW	RT				PRECAST WATER HOLDING TANK	6m x 3m SHELL COVER AND GENERAL NOTES SHEET	AS INDICATED AT A1	2017.0077	S400	C1
C1	16.12.2019	CONSTRUCTION ISSUE	MW	MC									
								CLIENT	ASSOCIATE CONSULTANT				
<p>LEVEL 9, 269 WICKHAM STREET, PO BOX 612 FORTITUDE VALLEY QLD 4006 AUSTRALIA T 07 3251 8555 F 07 3251 8599</p>													

- NOTE:
- STRUCTURAL DRAWING TO BE READ IN CONJUNCTION WITH S400 GENERAL NOTES DRAWING, S401 GENERAL ARRANGEMENT PLAN, S402 REINFORCEMENT PLANS DRAWING AND S403 TYPICAL INSTALLATION DETAILS DRAWING.
 - WEIGHT OF SHELL = 10.1t APPROX. (EXCLUDING REINFORCEMENT AND FINISHES)
 - SKIMMER BOX SETDOWN AND CAST-IN CONDUITS SETOUT TO BE CONFIRMED PRIOR TO POUR. SKIMMER BOX AND CONDUITS REQUIRED ONE SIDE ONLY.




PRECAST CONCRETE SWIMMING POOL GENERAL ARRANGEMENT PLAN

SCALE N.T.S




3D PERSPECTIVE VIEWS

CAST-IN LIFTING LUG INSERTS NOT SHOWN. REFER PLAN AND SECTIONS FOR LOCATIONS




DENOTES M20 x 70 LONG INSTALLATION LIFTING LUGS, REID ELEPHANT FOOT OR ANCON QWICKFOOT OR APPROVED EQUIVALENT. (STAINLESS STEEL) MAX WORKING SHEAR LOAD = 17kN (AT $f_c \geq 25 \text{ MPa}$) TO BE GROUTED UP AFTER INSTALLATION.

SECTION A
SCALE N.T.S



DENOTES M20 x 70 LONG INSTALLATION LIFTING LUGS, REID ELEPHANT FOOT OR ANCON QWICKFOOT OR APPROVED EQUIVALENT. (STAINLESS STEEL) MAX WORKING SHEAR LOAD = 17kN (AT $f_c \geq 25 \text{ MPa}$) TO BE GROUTED UP AFTER INSTALLATION.

SECTION C
SCALE N.T.S




DENOTES M20 x 70 LONG INSTALLATION LIFTING LUGS, REID ELEPHANT FOOT OR ANCON QWICKFOOT OR APPROVED EQUIVALENT. (STAINLESS STEEL) MAX WORKING SHEAR LOAD = 17kN (AT $f_c \geq 25 \text{ MPa}$) TO BE GROUTED UP AFTER INSTALLATION.


4 OFF Ø40 CAST-IN CONDUIT PENETRATIONS EVENLY SPACED, SHOWN INDICATIVELY. REFER NOTES

SECTION D
SCALE N.T.S


<p>LEVEL 9, 269 WICKHAM STREET, PO BOX 612 FORTITUDE VALLEY QLD 4006 AUSTRALIA T 07 3251 8555 F 07 3251 8599</p>	REV	DATE	DESCRIPTION	DESIGN	DRAWN	CHECKED	APPROVED	RPEQ No.	PROJECT	DRAWING TITLE	SCALES	
	P1	17.07.2019	PRELIMINARY ISSUE	MW	RT				PRECAST WATER HOLDING TANK	6m x 3m SHELL GENERAL ARRANGEMENT PLAN AND SECTIONS	AS INDICATED AT A1	
	C1	16.12.2019	CONSTRUCTION ISSUE	MW	MC							
									LOCATION	ARCHITECT	JOB NO	
									CLIENT	ASSOCIATE CONSULTANT	2017.0077	
											DRAWING NUMBER	REVISION
											S401	C1




PRECAST CONCRETE SWIMMING POOL BASE REINFORCEMENT PLAN
SCALE N.T.S




WALL W1 REINFORCEMENT ELEVATION
SCALE N.T.S




WALL W3 REINFORCEMENT ELEVATION
SCALE N.T.S



WALL W4 REINFORCEMENT ELEVATION
SCALE N.T.S
NOTE: REFER SECTION B ON DRG S101 FOR VERTICAL WALL REINFORCEMENT SETOUT AT STEPS.




SECTION B
SCALE N.T.S S401



TYPICAL INTERNAL TO EXTERNAL WALL DETAIL

DETAIL S1
SCALE 1:10 S402

DETAIL B1
SCALE 1:5 S402



TYPICAL WALL TO WALL MITRE CORNER DETAIL
WALL TO SLAB MITRE JOINT SIMILAR

- NOTES:**
- STRUCTURAL DRAWING TO BE READ IN CONJUNCTION WITH S400 GENERAL NOTES DRAWING, S401 GENERAL ARRANGEMENT PLANS, S402 REINFORCEMENT PLANS DRAWING AND S403 TYPICAL INSTALLATION DETAILS DRAWING.
 - SKIMMER BOX SETDOWN AND CAST-IN CONDUITS SETOUT TO BE CONFIRMED PRIOR TO POUR. SKIMMER BOX AND CONDUITS REQUIRED ONE SIDE ONLY.

LEGEND


- (1) ... DENOTES REINFORCEMENT LAID FIRST (AGAINST MOULD)
(2) ... DENOTES REINFORCEMENT LAID SECOND (EXTERNAL FACE)

BLIGH TANNER


LEVEL 9, 269 WICKHAM STREET, PO BOX 612
FORTITUDE VALLEY QLD 4006 AUSTRALIA
T 07 3251 8555 F 07 3251 8599

REV	DATE	DESCRIPTION	DESIGN	DRAWN	CHECKED	APPROVED	RPEQ No.	PROJECT	DRAWING TITLE	SCALES
P1	17.07.2019	PRELIMINARY ISSUE	MW	RT				PRECAST WATER HOLDING TANK	6m x 3m SHELL REINFORCEMENT PLAN AND SECTIONS	AS INDICATED AT A1
C1	16.12.2019	CONSTRUCTION ISSUE	MW	MC						
								LOCATION	ARCHITECT	JOB NO
								CLIENT	ASSOCIATE CONSULTANT	DRAWING NUMBER
										REVISION
										S402
										C1


LEGEND:
 T.W.L. TOP WATER LEVEL
 F.G.L. FINISHED GROUND LEVEL
 N.G.L. SOUND NATURAL GROUND LEVEL




TYPICAL POOL PLAN
 SCALE 1:50




TYPICAL POOL SECTION
 SCALE 1:50



SITE CLASS A/S/M




SITE CLASS H1/H2



SITE CLASS E - SITE SPECIFIC DESIGN REQUIRED

NOTE: DESIGN OF FOUNDATIONS FOR SITE CLASS E ARE SHOWN INDICATIVELY ONLY. FOUNDATIONS TO SUPPORT PRECAST SHELL IN SITE CLASS E ARE TO BE DESIGNED AND CERTIFIED BY A CERTIFIED ENGINEER.



BLIGH TANNER <small>LEVEL 9, 269 WICKHAM STREET, PO BOX 612 FORTITUDE VALLEY QLD 4006 AUSTRALIA T 07 3251 8555 F 07 3251 8599</small>	REV	DATE	DESCRIPTION	DESIGN	DRAWN	CHECKED	APPROVED	RPEQ No.	PROJECT	DRAWING TITLE	SCALES
	P1	17.07.2019	PRELIMINARY ISSUE	MW	RT				PRECAST WATER HOLDING TANK	6m x 3m SHELL	AS INDICATED AT A1
	C1	16.12.2019	CONSTRUCTION ISSUE	MW	MC					SITE CLASSIFICATION FOOTING OPTIONS	
									LOCATION	ARCHITECT	JOB NO
									CLIENT	ASSOCIATE CONSULTANT	2017.0077
											DRAWING NUMBER
									PLUNGE POOL COMPANY PTY LTD.	S403	C1